



NOTES:

1. METER SHALL BE INSTALLED IN HEATED UTILITY ROOM WITH FLOOR DRAIN.
2. BUILDER INSTALLS ELECTRICAL CONDUIT AND DBL GANG ELECTRICAL BOX AS SHOWN. PULL SIGNAL CABLE TO WITHIN 5 FT OF METER LOCATION WITH OTHER END IN ELECTRICAL BOX.
3. DENVER WATER WILL CONNECT SIGNAL CABLE TO METER AND INSTALL ERT ON ELECTRICAL BOX.
4. SEE SHEETS 50, 51 AND 52 FOR SERVICE AND SETTING DETAILS.
5. TOTAL LENGTH OF SERVICE PIPE FROM TAP AT MAIN TO WATER METER CANNOT EXCEED 60 FT.
6. MAX LENGTH OF SIGNAL CABLE IS 150 FT.
7. SERVICE PIPE MAY NOT BE PLACED BENEATH FLOOR SLAB; PLACE METER WHERE PIPE ENTERS BUILDING FOOTPRINT.

DENVER WATER

1800 West 12th Avenue • Denver, Colorado 80204
Phone (303) 628-6000 • Telecopier No. (303) 628-6851



INSIDE METER SETTING AND REMOTE ERT INSTALLATION FOR HOME BUILT ON SLAB

Scale: NONE Date: DECEMBER 2003

Drawn: C.B.B. Tr: Ck:

Approved: *[Signature]* Dr. 127 No. 35