

SECTION 11

11.20 INSPECTION DURING INSTALLATION:

Inspection of the installation of nonpotable mains will be made, but not limited to, at the following points of installation:

- A. Trench excavation and bedding.
- B. Placing pipe, fittings, and structures.
- C. Placing of nonpotable system identification devices.
- D. Pouring of all concrete anchors and thrust blocks.
- E. Placing and compacting the backfill.
- F. Tracer wire for locating PVC pipe.
- G. Pressure testing of transmission distribution mains and conduits.
- H. Flushing of lines prior to being put into service.
- I. Raising valve box covers to finish grade.
- J. Disinfection of the line prior to being put into service.